Notification dated 22nd April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 25th May 1936, for restoration of breached Byranahalli minor tank, Register No. 35, Narasapur Hobli, Malur taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.—

4. Each tender must be accompanied by a deposit of Rs. 200 (Two hundred) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Restoration of breached Byranahalli minor tank, Register No. 35, Narasapur Hobli, Malur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Progress to the extent of Rs. 600 has to be shown every month.

Abstract estimate for Restoring Byranahalli Kodagikere Register No. 35 of Malur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	I. BUND AT R.L. 53·50 TOP WIDTH 4½', SLOPES 1½ : 1 AND 2 : 1.				
1	Jungle clearing and removing ant hills and filling them with sand and cutting grips and trenches to bund	Grade	3 0 0	18	
2	Earthwork to bund with watering and consolidation	C.yds.	0 3 0	7,153	
3	Turfing the slopes of bund	S.yds.	0 0 9	3,376	
4	New stone work for pitching 1' in thickness ..	C.yds.	1 8 0	418	
5	Removing and Resetting old stone work ..	,,	0 8 0	175	
6	Providing and fixing new grade stones including figuring and painting, etc., complete ..	Each	1 8 0	18	
7	Do Index stones do ..	,,	0 6 0	18	
8	Do Reg. No. and Date stones ..	,,	3 0 0	1	
9	Do B.M. stones do ..	,,	2 8 0	2	
	BREACHED PORTION.				
1	Removing silt and sand in breached portion ..	C.yds.	0 3 0	240	
	(a) Excavation for puddle wall	,,	0 3 0	18	
2	Puddle wall for the centre of breach	,,	0 9 0	133	

No.	Item of work	Unit	Rate	Quantity	Cost
	II. CONSTRUCTING 6" CAST IRON PIPE SLUICE WITH CILL AT R. L. 46·50.		Rs. a. p.		
1	Earthwork cutting open the bund and refilling with consolidation	C.yds.	0 5 6	6	
	(a) Earthwork excavating for foundation ..	,,	0 3 0	7	
2	Stone Jelly concrete in surki mortar	C.ft.	0 4 3	166	
3	Burnt stone in surki mortar	C.ft.	0 5 0	207	
4	Burnt stone slabs, 6" thick, dressed and fixed ..	S.ft.	0 5 0	76	
5	Pointing with surki mortar	Sqr.	1 12 0	2·79	
6	Providing plug and rod with locking arrangements	L.S.			
7	Supplying and fixing 6" cast iron pipes, including Ry. freight	R.ft.	3 0 0	18	
8	Drilling holes in slabs	Each	0 8 0	2	
9	Rough stone drain	C.yds.	1 8 0	7	
	III. CONSTRUCTING A WASTE WEIR AT 50·00, 190 FEET LENGTH.				
1	Earthwork Excavation	C.yds.	0 3 0	121	
2	Stone jelly concrete in surki mortar	C.ft.	0 4 3	414	
3	Burnt stone in surki mortar	,,	0 5 0	494	
4	Burnt stone slabs, 6" thick, dressed and fixed ..	S.ft.	0 5 0	767	
5	Pointing with surki morter	Sqr.	1 12 0	9·33	
6	Rough stone work, new	C.yds.	1 12 0	78	
7	Joggle joints	Each	0 12 0	24	
	Total Rupees for Waste Weir ..	..	..	..	..

Notification dated 22nd April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 25th May 1936, for restoration of Thirumaldevarapalli Thirumaldevarkere, Register No. 365 Minor, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and fifty (Rs. 150) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoration of Thirumaldevarpalli Thirumaldevarkere Register No. 365 of Bagepalli Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific terms of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Progress to the extent of Rs. 500 has to be shown every month.

Abstract estimate for Restoring Thirumaladevarapalli Thirumaladevarakere, Minor Tank, Register No.365 of Bagepalli Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	I. BUND : R.L. 55·00.				
1	Earthwork to bund including watering and tamping, etc., complete	C.yds.	0 3 0	2,310	
2	Turfing to bund	S.yd.	0 0 9	2,008	
3	New stone work	C.yds.	1 8 0	470	
4	Old stone work	,,	0 8 0	154	
5	Gravel backing	,,	0 8 0	328	
6	Grade stones	Each.	1 8 0	8	
7	Index stones	,,	0 8 0	8	
8	B.M. Stones	,,	3 0 0	2	
9	Register No. stone and date stone	,,	3 0 0	1	
10	Gauge stone	,,	15 0 0	1	
11	Clearing thick jungle	Gr.	5 0 0	7½	
12	Cutting trees	L.S.			
13	Cutting grips and trenches	Gr.	2 0 0	7½	
14	Sundry works	L.S.			
	Total Rupees for Bund	..	..	..	..
	II. SLUICE.				
1	(*a*) Cutting bund	C.yds.	0 3 0	54	
	(*b*) Closing the gap	,,	0 3 0	54	
2	Jelly concrete in surki mortar	C.ft.	0 4 0	419	
3	Burnt brick in surki mortar	,,	0 4 6	501	
4	Burnt stone slabs, 6" thick dressed	S.ft.	0 5 0	244	
5	Surki plastering	Sqr.	4 0 0	5·83	
6	Apron for rear of tunnel	L.S.			
7	Locking arrangements	,,			
8	Providing plug and rod	,,			
9	Cutting grooves in cross slabs	,,			
10	For other sundries	,,			
	Total Rupees for Sluice Repairs	..	..	..	..
	III. WASTE WEIR.				
1	Blasting rock	C.yds.	2 0 0	230	
2	Benching rock	S.ft.	0 12 0	114	
3	Burnt stone slabs, including joggles	S.ft.	0 5 0	114	
4	Burnt brick in surki mortar	C.ft.	0 4 6	100	
5	Concrete in surki for gaps after	L.S.			
6	Providing gibbet walls and shutter for gap in the weir	,,			
	Total Rupees for Weir ..	..	..	..	..

N. SUBBA RAO,
Executive Engineer.